## **Executive Summary**

COVID-19 has posed unprecedented challenges to the construction industry around the world. Building is an inherently hands-on activity, which requires people to be on site, working collectively. With some exceptions, construction is generally not considered an essential service, and has therefore been stopped in many locations. In some places, sites are already going back to work; in others, we are poised to restart under difficult and unprecedented conditions. How can we begin to manage construction processes, while keeping people safe and also minimizing lost productivity? This document is our first attempt to answer that question.

As leaders on construction projects, our responsibility is to safeguard the health and wellbeing of those on our sites and those affected by our work. The construction industry can play a major role in the economic recovery. To do so, we must demonstrate that sites can re-open and continue building without jeopardizing worker or community safety.

This document was developed in the context of the Rwandan construction industry. A key characteristic of the industry in Rwanda is a particularly large workforce on job sites due to reliance on manual labor over mechanization. It is important to recognize that there can be a lot of variability in construction sites and project delivery situations, and best practices may need to be adjusted to suit imperfect real world circumstances. These guidelines are a first attempt to understand how best practices may be applied in our particular context. We have developed them for use on our own sites, and will be testing, reviewing, and revising them over the coming weeks and months.

We have addressed key issues related to infection control including: Physical distancing, personal hygiene, cleaning and disinfection, supervision and enforcement, and community education. The aim of this document is to explore how these principles may best be applied in practice. As we become more informed by on-the-ground experience in the coming weeks and months, this document will be updated to reflect what we learn.

### Introduction

Construction sites operating during the COVID-19 pandemic need to ensure they are protecting their workforce and minimizing the spread of infection as a matter of global public health. These guidelines are intended to serve as recommendations for third party contractors and protocols for construction sites under the supervision of MASS Design Group. All contractors and staff must comply with the latest Government of Rwanda and WHO advice and/or direction on the prevention of spread of coronavirus at all times, which may be updated with more frequency than this document and should be regularly consulted.

If an activity cannot be undertaken safely, whether due to a lack of suitably qualified personnel or supporting resources required to provide a safe system of work, or because of restrictions imposed by infection control requirements, it should not take place.

We have addressed key issues related to infection control including: raising awareness, physical distancing, personal hygiene, cleaning, disinfection, supervision, and enforcement.

#### **Purpose and Use of this Document**

This document is intended for use by project leadership, including Site Managers, Health, Safety & Welfare Officers (HSW), and others in a position of leadership or influence on the construction site. Project leadership should use this document as a guide to develop written, project specific plans for operations during this period.

It is expected that project leaders will then train others, including Team Leads, Foremen, and Site Engineers, to conduct the works safely and in a manner consistent with infection control requirements.

MASS DESIGN GROUP Kigali Heights Plot 772, KG 7 Ave Kacyiru, Kigali

kigali@massdesigngroup.org +250 723 571 138

massdesigngroup.org

## Section Overview

1.0 Raising Awareness	Includes guidance on training, symptomatic person response, and community health. This section should be used by project leadership and HSW officers to develop training materials and other educational sessions for the site workers.
2.0 Site Access	Includes guidance on commuting protocols, site entry and exit sequences, and screening/ testing procedures. This section should be used by project leadership and HSW officers to establish protocols for shift start/finish times.
3.0 Physical Distancing	Detailed recommendations around physical (or social) distancing, how to best apply those requirements to task planning and site organization. This section should be used by project leadership and HSW officers to establish protocols for work procedures on site, inform project schedules, and develop training sessions for foreman and site engineers. The content of this section should also be disseminated to the general workers for awareness via toolbox talks, posters or other similar means.
4.0 Personal Hygiene	Includes recommended practices for handwashing, Personal Protective Equipment (PPE), site welfare facilities, and water and food provisions. This section should be used by project leadership and HSW officers to plan for additional required facilities or equipment on site, order and maintain supplies of PPE and other necessary products. The content of this section should also be disseminated to the entire project team for awareness via toolbox talks, posters, or other similar means.
5.0 Cleaning and Disinfection	Includes recommendations and procedures in line with guidance on limiting infection through highly contacted surfaces or objects. This extends from surfaces, to equipment, to construction materials themselves. This section should be used by project leadership and HSW officers to plan for additional required facilities or equipment on site and to develop training sessions for foreman and site engineers. The content of this section should also be disseminated to the entire project team for awareness via toolbox talks, posters, or other similar means.
6.0 Planning and Implementation	Includes recommendations for effective planning and implementation of the guidelines and protocols contained within this document. This includes risk assessment and mitigation as well as task planning and site organization. This section should be used by project leadership and HSW officers to plan how to effectively implement the guidelines and protocols contained within this document.
7.0 Supervision and Enforcement	Includes recommendations to support the effective use of these protocols and how to continuously improve and enforce them. This section should be used by the project leadership (contractors and consultants) and HSW officers to support them in their effort to fairly and unbiasedly enforce these guidelines.
8.0 Additional Resources	Contains additional resources from governmental, public health, and industry specific sources. Organized by source and location, the links can be used to add more detail or context to the information contained herein.
9.0 Roles and Responsibility	Contains a description of each person's role and responsibilities in contributing to the successful implementation of these guidelines as well as a checklist for each role which can be used regularly to ensure that all protocols are being followed.

## 1.0 Raising Awareness

Best practice in health and safety has long demonstrated that people are more likely to comply with requirements if the reasons behind them are understood. Raising awareness of the risks from COVID-19 and training personnel to take appropriate precautions are vital steps in combating onsite transmission.

This section covers the fundamentals of training, symptomatic person response, and mental health support. In recognition of the potential for infections being passed between the construction site and the surrounding community, guidance is also given on community engagement and keeping the family safe.

### 1.1 Training

Ensure that anyone entering the site is informed of the general characteristics of COVID-19, focusing on why precautions are needed and why the illness should be considered as a serious threat.

- · Symptoms and the conditions that put an individual at higher risk
- · Worldwide status e.g. number of cases, number of deaths
- · Situation in Rwanda
- · Responsibilities of the individual to their colleagues, family & community

Provide a series of printed posters throughout the site explaining symptoms and response protocol.

Provide information on precautions that should be taken, including:

- · Physical Distancing
- · Personal Hygiene
- Personal Protective Equipment

Hold daily briefing sessions to be in small groups of team size - refer to Section 6.4 to provide updates and reminders on health and safety protocol

# 1.2 What to do if someone has symptoms

Each employee is responsible for self-certifying prior to shift if they:

- Have experienced symptoms within the past 24 hours.
- · Have had "close contact" with an individual diagnosed with COVID-19.
- · Have been asked to self-isolate or quarantine by their doctor or a local public health official.

If a worker develops a high temperature or a persistent cough while at work, they should:

- Return home immediately.
- If in Rwanda, self-report via 114 hotline and follow MoH advice.
- · Avoid touching anything.
- Cough or sneeze into a tissue and put it in a bin, or if they do not have tissues, cough and sneeze into the crook of their elbow.

Emplyees must then follow the guidance on self-isolation and not return to work until their period of self-isolation has been completed.

Provide MoH access to records of teams, crews, and work-zones if requested to facilitate contact tracing if required.

Contractor to carry out risk assessment considering infected cases and risk to overall workforce health with active site.

## 1.3 What you can do at home

Talk to your family about the risks, see Section 8.0 for guidance/posters.

Practice good personal hygiene, especially hand washing.

Make sure family members are following government guidelines - guma murugo!

## 1.4 Community Engagement

Communicate to workers about a responsibility for their own health and for the health of their families and communities.

Engage with communities, local partners, and other stakeholders to help prepare and protect individuals, families and the public's health during early response to COVID-19. Communication to workers about COVID-19 updated preventive measures in the community.

Workers should know who they will inform at work if there's a COVID-19 case in the neighbourhood.

### 1.5 Mental Health

Contractor should consider additional support for mental health and psychological well-being during COVID-19 outbreak.

Toolbox talk focusing on stress management, depression, and suicide prevention. Resources
are available from the <u>Construction Industry Alliance for Suicide Prevention</u>.

Prevent and address the social stigma surrounding those who have been infected.

Maintain privacy of all workers during screening, testing, reporting, etc.

#### 2.0 Site Access

Access to site must be controlled in order to limit the risk of infection being brought in from outside. Reducing numbers of personnel to only those who are essential for works to continue will also make it easier to maintain physical distancing (Section 3.0) and hygiene protocols (Sections 4.0 and 5.0).

#### 2.1 Travel to Site

Transport to site needs to be in line with the latest government & police guidelines.

Where not prevented by legal restrictions, the following should be considered:

- Wherever possible people should travel to site alone using their own transport.
- Where personal transport is not possible, avoid public transport/motos and try to taxi or carpool while minimizing the number of people in the car (e.g., one person per row of seats).
- If hiring a driver, drivers should remain in their vehicles if possible. If leaving the vehicle, the driver must wash or sanitise hands.

# 2.2 Reduce Non-Essential Presence

Stop all non-essential visitors and vendors. Issue specific guidance for deliveries:

- Drivers should remain in their vehicles, if the load will allow it. If required to unload goods or materials themselves, they must wash or clean their hands before unloading.
- Consider developing an electronic signature system with suppliers to reduce physical interaction, for example email or WhatsApp.

Review method statements and reconsider construction processes with a view to completing works with as few people as possible, resulting in an overall reduction in the number of people on site, refer to.

## 2.3 Site Entry/Exit

Monitor site access points to enable physical distancing. Site leadership may need to consider changing the number of access points - either increasing to reduce congestion or decreasing to enable monitoring and consider staggering start time to avoid congestion.

Security personnel to have a list of approved visitors. Daily attendance log of all workers and visitors must be kept and retained for at least 4 weeks. The log must include the name, phone number, and home address of all workers and visitors.

Observe all social distancing, hygiene, and sanitation protocols.

It is recommended that construction workers are not allowed to leave the site during working hours and are therefore provided with all essential items e.g. food (Section 4.7).

## 2.4 Testing and screening at site

Ensure public health information is accessible by workers (e.g. posters in local languages) to inform of systems and expected protocols.

Screening is out of public view to respect privacy and results are kept private.

Anyone who meets one of the following criteria should be turned away from site:

- · Has a high temperature or a new persistent cough.
- Is a vulnerable person (by virtue of their age, underlying health condition, clinical condition, or are pregnant).
- Is living with someone in self-isolation or a vulnerable person.

Temperatures shall be checked by infrared thermometer before entering site, The checker must have a mask, eye protection (or full face shield), and gloves.

## 3.0 Physical Distancing

Global authorities recommend that a minimum of one to two meters distance between individuals be maintained at all times to limit the risk of COVID-19 transmission. This document considers 2m (two meter) minimum to be the appropriate standard. It is recommended that construction sites establish this as a minimum requirement for all work activities, break times, and when travelling to and from site. This section provides practical recommendations for maintaining physical distance on a working construction site.

## 3.1 Physical Distancing Norms

Keep a 2m distance between individuals at all times. This includes during work activities, commuting to the site, and during breaks.

# 3.2 Task planning to minimize interaction

Review and revise all Method Statements for work deemed at risk to transmission of disease. Criteria to be considered in Method Statement review:

- Potential Impacts of Physical Distancing Recommendations
- Tool and equipment communal use transitioning to individual use
- Need for frequent hygiene and disinfection work stoppages
- Any alterations to work practices, processes, or tasks organization should be considered in the Hierarchy of Control to best limit potential disease spread:
  - 1. Elimination (can we completely eliminate the task?)
  - Substitution (can we substitute the task for something else? E.g. instead of mixing concrete on site, have ready-mix delivered.)
  - 3. Engineering Controls, refer to Section 6.2
  - 4. Administrative Controls, refer to Section 6.2
  - 5. Safe Work Practices
  - 6. Personal Protective Equipment (PPE)

Enforce physical distancing through task organization, for example:

- Marking 2m distance physically around key points.
- Limit interaction between people wherever possible, especially porters, laborers, and cleaning staff.
- Diagrams around specific tasks (e.g. reinforcement fixing, masonry, concrete pouring). Refer to Appendix A.

### 3.3 Common areas

Reconfigure designated break areas so that people can sit 2m apart, limit number of people per area according to team or crew size.

Arrange for lunch breaks to be taken in shifts and/or organise enough sheltered areas for appropriate social distancing to be possible.

# 3.4 Use of tools and equipment

Limit sharing of tools and any multi-user devices (iPads, radios, etc.)

Limit exchange of paper documents on site: all workers that require drawings should be provided with their own drawings. Consider lamination where possible.

#### Tools

- Small tools: Not shared. Workers will have individual tools and have dedicated areas for storage.
  - If small tools are stored on site they should be stored in small teams/trades and/or by activity.
- · Large tools: Should be used only in a defined 'path' that is limited to prevent transmission.
  - For example, wheelbarrow moves between point A and B, but does not enter the zone of either area.
  - 2. Only utilized by select teams, monitored/recorded daily.
  - 3. Depending on use and frequency, should be disinfected more frequently.

#### **Equipment and Plant**

- To be operated by the minimum number of workers to safely perform task wherever feasible.
- · Consider dedicating equipment and plant to site zones to prevent further transmission.

## 4.0 Personal Hygiene

The World Health Organisation recommends enhanced personal hygiene to prevent transmission of COVID-19. It can be difficult to ensure and enforce such measures on a construction site, owing to the physical nature of the work. It is therefore essential that the Contractor plans the site and the works so that all personnel have access to basic precautions such as handwashing facilities and personal protective equipment. This section also gives guidance on essential welfare provision such as toilets, drinking water and food.

### 4.1 Provisions Checklist

Before beginning work on site, all necessary PPE and access to disinfectant must be available to everyone on site. Create a checklist to be used daily to ensure these measures are in place.

## 4.2 Hygiene Protocols

Wash hands frequently with soap and running water. Dry hands with single-use paper towels.

Clean and disinfect chairs, tables, and other communal surfaces.

Do not share tools or accessories (including iPad, laptops, cell phones).

Limit the exchange of paper documents (encourage electronic communication). Laminate where possible to increase longevity and allow for disinfection.

## 4.3 Personal Protective Equipment (PPE) Requirements

In addition to all reasonable efforts to eliminate risks to the worker, PPE should be employed to further reduce risks.

Eye Protection, gloves, and masks should be worn at all times on construction sites by all parties as a COVID-19 protection measure, not just those who would typically require it for their work tasks

- The type of glove worn should be appropriate to the task. If gloves are not typically required
  for the task, then any type of glove is acceptable, including latex, non sterile, or disposable
  gloves.
- Masks may make it more difficult to work. Safe work times should be determined based on the intensity of the task being performed and the overall health of the worker.
- Eye Protection, gloves, and masks should be disposed of after each use, unless of a reusable type, in which case they should be sanitized daily.
  - 1. Instruct workers to wash hands after removing gloves.
  - 2. Proper techniques for putting on and removing masks can be found here.

All workers should receive instruction on how to properly put on and remove PPE and on sanitation of PPE.

To ensure proper sanitization, the contractor should ensure access to adequate PPE.

- Disposable PPE should only be used once. Reusable PPE should be properly sanitized between uses.
- · Sanitization procedures should follow manufacturer recommendations.
- Hard hats and vests should be sanitized regularly. Manual or machine washing should be used where appropriate.
- Proper waste receptacles should be available at key locations for disposal of PPE.

PPE should not be shared between workers unless it has received a proper sanitization.

### 4.4 Hand Wash Stations

Distributed throughout the site/work area in common areas such that workers can wash hands frequently without significant loss of work time.

- · Hand washing stations should have soap and running water.
- It is important to provide a means of hand drying as germs can be transferred more easily to and from wet hands. Suggest providing single-use paper towels. Avoid shared towels.
- · Equip with a waste receptacle.
- Handwashing stations should be foot pedal operated.
- · Provide proper handwashing diagram guidelines at each sink.
- Alternatively, alcohol-based hand sanitizer can be used (ensuring it contains at least 60% alcohol).

A system for notification of low supplies should be implemented without the need for close human contact.

Optional: Utilize shoe sanitation tubs (non-bleach sanitizer solution) prior to entering/leaving job site, but only if the replenishing of sanitation tubs can be well-managed.

#### 4.5 Toilets

Implement one-in one-out controls.

Ensure hand washing is available at all toilets.

Review number of people per toilet. Depending on site specifics, consider adding additional facilities to limit the number of people using any single location.

## 4.6 Drinking water

Drinking water shall be provided, as required by law, and in a way that complies with all social distancing, hygiene, and cleaning and disinfection protocols.

• E.g. individual bottles, assigned personal vessels, foot operated dispenser, etc.

### 4.7 Food

Eliminate non-essential communal items such as coffee pots.

All food should be served in individual containers prepared and packaged with infectious disease prevention controls in place .

The contractor should provide meals to workers to minimize interaction with outside parties. Consider having food:

- · Delivered by a vendor in individual containers.
- Cooked on site and distributed in individual containers.

# 5.0 Cleaning and disinfection

The World Health Organization states that touching contaminated surfaces is one of the main transmission routes for COVID-19. Additional cleaning and disinfection of surfaces and shared items such as tools is therefore very important for risk reduction on construction sites. This section provides guidance on cleaning requirements and frequency, as well as recommendations for dealing with shared equipment.

### 5.1 General Procedures

All frequently touched surfaces, or those with potential for exposure should be frequently cleaned.

- Disinfect tables, seating, or any other surfaces (if there are any) after each group leaves area.
- Door knobs and frames, counters or work surfaces, washing stations, water stations, toilet facilities, etc.
- Special attention should be paid to non-porous surfaces, where droplets can remain active for up to 72 hours.
- Suggested frequency of cleaning is at least twice daily or between shifts, or more often where the number of users is high.

Toilets to be cleaned frequently.

 Particular attention paid to soap dispensers, door locks, and flush handles. Cleaning frequency to be discussed, taking into consideration the number of users. Suggestions include hourly or after each shift.

Waste - utilise foot pedal operated waste receptacles. Personnel responsible for removing waste must wear full PPE & use hand washing practices.

Ensure sufficient cleaning staff are available to maintain cleaning frequencies as described.

## 5.2 Tools and equipment

If tools must be shared, they should be cleaned between each use/user.

- For tools that are not sensitive to water, a bucket of water mixed with bleach (30:1 ratio
  minimum) can be used to dunk and sanitize the piece. Towels can be available for drying to
  prevent rust.
- For tools that are sensitive to water (i.e. electric power tools or similar), disinfecting wipes can be used. If not available washable cloth towels soaked in water bleach mixture can be used (Note: these should be treated as single use and thoroughly washed before re-use).
- For larger tools (ladders, wheelbarrows, scaffolding, etc), spraying a water/bleach mixture
  can also be used to disinfect. The solution must sit undisturbed on the surface for 5 minutes
  to kill all the germs.

For heavy equipment and fleet vehicles (including Fiori Mixers, Bobcats, HDPE welders, etc) surfaces and high contact areas should also be regularly disinfected at least once per shift or whenever the driver changes.

- 1. Be sure to include steering wheel, gear shift, instrument panels, etc.
- Replace cabin air filters if you suspect they have been exposed or compromised by sick employees.
- 3. Must be fully disinfected before and after any required maintenance.

The contractor should determine the best means of enforcing this (i.e. after each use, before each use, or by a person/party dedicated for sanitization).

### 5.3 Construction materials

Due to the nature of most construction activities, it may be difficult, impractical, or damaging to disinfect construction materials. The contractor should review the possibility for this as part of each task's Method Statement to determine where disinfecting procedures could be applied.

Spray or wipe materials where possible with disinfecting solution. To limit damage, this should be done first as a test and results observed.

Disinfecting of materials should be considered where multiple handling is required, and can be introduced between natural steps in the process.

# 6.0 Planning and Implementation

Health and safety on construction sites can be difficult to control. Clear procedures for supervision of the workforce will improve chances of successfully reducing the risks from COVID-19.

This section covers administrative measures such as risk assessments, site zoning, reporting and works scheduling which the Contractor can adopt to improve workforce compliance with the new safety procedures.

#### 6.1 Risk Assessments

Risk assessments are required for all tasks - but especially tasks for which physical distancing requirements would be difficult to meet.

In addition to assessments by task, risk assessment are also to be carried out at project level:

- · Identify activities that are essential to continue.
- · Identify activities that can be halted/delayed.
- · Identify staff that are at greater risk, or staff who have concerns with continuing work.
- Define conditions under which the project will need to stop and potential impacts that may arise from that stoppage.

Review the clear chain of communication within staff (especially HSW). This should include communication with all stakeholders (owner, supervisor, subcontractors, etc).

### 6.2 Risk Mitigation

Implement engineering controls such as:

- · Installation of physical barriers between workers.
- Use of mechanical or plant transportation in lieu of manual methods.
  - Limit or avoid 2-man lift operations. Use forklifts, telehandlers, or similar equipment where possible.
  - 2. Consider moving/transporting less material per trip and increasing trip count to allow for a single person to accomplish tasks.

Installation/implementation of ventilation in enclosed or confined areas. This is an effective means of controlling hazardous exposures and could be comprised of any of the following:

- 1. Ductwork
- 2. Fans
- 3. Air Cleaning Device used in conjunction with items A and B
- 4. Other means of increased airflow and exhaust from the space

Implement administrative controls such as:

- · Rescheduling or delaying non-essential tasks/work.
- Limiting workers numbers per shift.
- On larger sites introduce staggered start and finish times to reduce congestion and contact at all times.
- · Stagger work areas to increase distance and limit potential for group mixing.

## 6.3 Zoning the Site

Develop a zoning map for the site and establish groups of workers for each zone.

Each zone should have a defined crew per trade to limit movement across site. Wherever possible, do not 'stack' trades.

Zone-based color cards (e.g. yellow, green, and blue each representing different zones) could be disseminated to every worker to help to control the number of people moving between zones and aid in personnel management on site.

Ensure means of welfare, hand-washing, and disinfection present in each zone.

### 6.4 Groups

The following hierarchy of group size may be used to plan activities appropriately, depending on the size of the site.

- Individuals
- Buddies (2-3): May be appropriate group size for vehicular travel.
- Team (5-10): Appropriate size for toolbox talks, eating in shifts etc.
- · Crew (10-30): Recommended maximum number of people for each HSW representative.
- Shift (30+): Maximum number of people on site at any given time.

Assign dedicated HSE Representatives per crew to enforce recommendations and monitor progress. This could be any or all of the following:

- 1. One HSE rep per zone/crew per activity
- 2. One HSE rep per 20 people
- 3. Defined exactly in Risk Assessment completed by Contractor

Any typical meetings (Toolbox Talks, etc) to continue at a team level while maintaining social distancing of 2m or more.

Ensure space for anyone on site to report concerns candidly, and encourage people to speak up. May be face to face communication, or for example a virtual suggestion box through a dedicated SIM to receive SMS, or similar.

Keep daily records of assigned teams, crews, and work zones to facilitate contact tracing if required.

### 6.5 Schedule of Works

Contractor to provide a clear schedule of works and required inspections. This should be updated on a weekly basis with daily check-ins regarding pending works.

- Site Supervisor or Consultant to agree if the site inspection is required (considering importance of the task, time critical nature, and risks if the works continue without inspection).
- Contractor will need to be proactive in arranging the required inspections by a supervisor or 3rd party where access to the site may not be as regular.
- · Work happening in each zone (activity and estimated number of workers per activity).
- Procurement, exemptions or authorizations, workforce limitations, or other gating items that could pose schedule impacts (short term and long term).

Anticipate resources needed for each day for each zone. Wherever possible, materials (mostly consumable) are to be pre-located in the zone where the activity is scheduled to take place the following day. Materials stored or moved from zone to zone should be disinfected consistent with Section 3.0.

# 6.6 Additional Reporting by the Contractor

Contractor to send daily email for quick review of the day's activities and progress in accordance with the planned schedule, both to:

- Monitor Health and Safety (H&S) and Quality Assurance/Quality Control (QA/QC.)
- Report any person with COVID-19 symptoms and any cue that can indicate potential presence of COVID-19 infection or potential spread. Refer to Section 6.0 for more information.

Contractor to supplement weekly report to include:

- General H&S data (number of workers employed, incidents occured, general site conditions, key H&S & QA actions taken over the course of the week).
- Update on the COVID-19 measures in place during the week.
- Difficulties that may have been met with regards to infection control (what worked versus what did not) for review and adjustment.
- Key aspects to look out for in the upcoming week.

### 6.7 Meetings

Do not hold, or participate in site-wide meetings, stand-downs, celebrations, or meals.

Reduce physical meetings, and use video conferencing wherever possible.

Limit meetings to less than 10 people, hold all meetings outside, with attendees all stand 2m apart (draw 2m spaced dots on ground).

# 6.8 Fire evacuation procedures

Review fire evacuation procedures. Consideration must be given to how quickly the site can be evacuated whilst maintaining social distancing, and how to maintain distance at a muster point.

# 7.0 Supervision and Enforcement

7.1 Evaluation

Based on risk assessment and risk mitigation (sections 6.1 and 6.2) the activities should be continuously evaluated to determine if the mitigation techniques are working effectively. Consider:

- Daily reviews with anyone responsible for implementing protocols including construction supervisor.
- Go / no go decision meetings at key points when staffing numbers are going to be increased or a new activity will be undertaken.
  - See the **COVID** site visit decision process
- Establish process for receiving feedback and adapting protocols based on feedback.
- · Seek input from independent or 3rd parties (supervisor or others).

#### 7.2 Empowerment

Ensure that the fore(wo)men, site engineers, HSW personnel, supervisors, and leadership are empowered to access adequate resources, and implement necessary changes, without further approval, to enforce the preventative measures in this document.

• No one should be reprimanded or punished for raising concerns about safety.

### 7.3 Enforcement

If any person, team, or crew continually disregards the protocols and regulations despite being advised of how to conduct themselves in compliance with them consider taking the following actions:

- Ask the individual or group why they are violating the protocols. If there is a legitimate
  reason, the protocols or tasks should be adapted to ensure that compliance is reasonably
  achievable.
- For individuals, implement a three strikes program after three strikes the person is suspended from working on site until the risk has subsided.
- For groups, change the people who are responsible for monitoring and enforcing the protocols.

## 7.4 Behaviour of Supervisor

#### **Provisions Checklist**

 Utilize a checklist to ensure all necessary equipment and resources are available. See Section 9.0: Roles and Responsibilities.

Limit time spent on site to essential tasks only by considering what tasks are critical and require physical presence.

Document the behaviour from a safe distance and submit report to contractor's health and safety officer.

Ensure that your involvement does not interfere or inhibit the contractor from implementing protocols.

If there is a perceived risk to personal safety, vacate the site/zone.

#### 8.0 Additional Resources

The situation surrounding COVID-19 is rapidly changing. In light of our own experiences, we have developed the content here, heavily informed by our colleagues across the construction industry and in public health. Linked below are a variety of sources that should be checked regularly as the situation evolves. We have included a broad range of contexts to help contractors, supervisors, architects, and engineers respond to their particular situations and conditions.

#### 8.1 Government of Rwanda

- Ministry of Health: Most up-to-date information on the situation in Rwanda
- · Rwanda Biomedical Center: Specific guidance for infection control in Rwanda
- Hospital Contact Information by Geography

<u>8.2 World Health Organization</u>: Global guidance on infection control. In depth and detailed procedures for disinfection, symptomatic response.

8.3 Centers for Disease Control (USA): American government guidance, includes helpful guidance on PPE and symptomatic response.

PPE Guidance

8.4 Scottish Government: Comprehensive guidelines specific to the construction industry.

8.5 Workplace Denmark: Comprehensive guidelines specific to the construction industry.

8.6 HSE UK: Comprehensive guidelines specific to the construction industry.

<u>8.7 Association of General Contractors (ACG):</u> Varied guidelines focused on the construction industry. Includes general national/statewide guidance and specific contractor COVID-19 response plans.

8.8 State of Massachusetts (USA): General guidelines specific to the construction industry.

8.9 <u>OSHA</u>: Extremely detailed and comprehensive guidance on workplace safety, in general and specific to construction sites.

- Guidance on Preparing Workplaces for COVID-19
- Strategies to Optimize the Supply of PPE and Equipment
- Respiratory Protection eTool

8.10 For examples of posters and graphic guidance to develop for your site or office:

- Rwanda Biomedical Center (via WHO)
- Office of the Prime Minister of Rwanda Notice on COVID-19 (kinyarwanda version)
- World Health Organization
- · Centers for Disease Control
  - · Stop the Spread of Germs
  - Symptoms of Coronavirus
  - Prevent the spread of COVID-19 if you are sick
  - What You Can do if You are at Higher Risk of Severe Illness from COVID-19
  - 10 things you can do to manage your COVID-19 symptoms at home

## 9.0 Roles and Responsibilities

#### Worker

- Skilled or unskilled workers, for example masons, carpenters, electricians, welders, porters, cleaners.
- · May work alone or in small teams.
- May be employed directly by the main Contractor, or by a sub-contractor.

#### **Team Leader**

- Responsible for a small group of workers, usually performing a defined task or trade. For
  example, supervising masons working on walling for a single small building or section of a
  larger building.
- Typically responsible for up to X workers.

#### **Foreman**

Responsible for technical supervision of sections of the works. May supervise a defined trade or may be responsible for an area of the site.

#### Site Engineer

Responsible for technical implementation and potentially management tasks such as scheduling and procurement, for the whole or part of the works.

#### **HSW Officer**

Responsible for ensuring the health, safety and welfare of workers and the general public. Works with Site Manager, Foremen, Workers and other key technical staff (for example Site Engineers) to identify risks resulting from the works, and to define and implement measures to eliminate or reduce those risks. Also responsible for monitoring health and safety conditions on site.

#### Site Manager

- Responsible for the overall management of the site, including resource management, procurement, work scheduling and quality control. Ultimately responsible for all health, safety and welfare issues.
- May delegate elements of administration (for example writing risk assessments and method statements) but retains ultimate responsibility.

#### Site Supervisor

An external party, typically an Architect or Engineer, responsible for technical oversight of the works. Under Rwandan law, the Site Supervisor holds significant responsibilities for quality control and health and safety during construction.

Umukozi ukora	Inshingano za buri munsi U	munsi	1	2	3	4	5	6	7
bubyizi Amazina	<ol> <li>Irinde kuza mu kazi mu gihe wumva urwaye cyangwa utameze neza, by' umwihariko mu gihe inkorora cyangwa umuriro.</li> </ol>	e ufite							Г
Amazina	<ol> <li>Ubahiriza ibisabwa mbere yo kwinjira ahakorerwa imirimo y'ubwubatsi, harimo gufatwa igipi cy' umuriro ndetse no gukaraba intoki uko bikwiriye.</li> </ol>	imo							
lgihe yatangiriye akazi	3. Karaba intoki zawe kenshi ku munsi, ukoresheje isabuni n' amazi meza byibuze umare igihe o amasegonda 20 (makumyabiri) ukaraba. Umutsa intoki zawe nyuma yo gukaraba.	cy'							
Ufite inshingano zo	4. Siga nibura intera ya metero 2 (ebyiri) hagati yawe n' abandi igihe cyose. Mu gihe bidashobo kubera imiterere y' umuriro uri gukora cg se imiterere y' aho uri gukorera, bimenyeshe ukuri itsinda cg umuyobozi ushinzwe imirimo yo kubakisha.								
gusigasira ubuzima bwawe, ubwa bagenzi bawe, ubw'umuryango wawe ndeste n' ubw' umuryango	<ol> <li>Ambara ibikoresho by' ubwirinzi wahawe nkuko bisabwa. Kurikiza amabwiriza agenga uko ibikoresho by' ubwishingizi byambarwa, uko ubyiyambura ndetse nuko ubikorerwa isuku. Irir gutiza abandi ibikoresho byawe by' ubwirinzi.</li> </ol>	nde							
	6. Irinde gutizanya ibikoresho keretse gusa mu gihe byasukuwe hakoreshejwe imiti yabugenew	ve.							
nyarwanda.	7. Irinde gutizanya ibikoresho unyweramo, amasahani cg ibindi bikoresho byo ku meza.								
	<ol> <li>Mu gihe ubonye ibikorwa bitubahiriza amabwiriza yo kwirinda Koranavirusi (COVID-19), men- umuyobozi w' itsinda, umuyobozi ushinzwe imirimo yo kubakisha cg umukozi ushinzwe ubu: bw' abakozi n' umutekano.</li> </ol>								
Kwita ku buzima bw' umuryango wawe, n' ubwu	<ol> <li>Ganiriza umuryango wawe kuri Koronavirusi (COVID-19). Kora ku buryo basobanukirwa neza uburyo yandura n' ibimenyetso biburira byayo.</li> </ol>								
muryango nyarwanda.	2. lyuhagire umubiri wose ukigera mu rugo.								
	3. Siga buri gihe intera hagati yawe n' abandi mu gihe utari ku kazi. Irinde kujya ahantu hateran abantu benshi.	nira							
	4. Mu gihe aho utuye hagaraye ufite ibimenyetso biburira bya Koronavirusi (COVID-19), ihutire		$\overline{}$	$\overline{}$	$\overline{}$		$\overline{}$	$\overline{}$	$\overline{}$

kubimenyesha umuyobozi wawe w' itsinda cg umuyobozi ushinzwe imirimo yo kubakisha.

Worker	Key Daily Responsibilities	Day	1	2	3	4	5	6	7
VVOIRGI	Do not come to work if feeling ill, and particularly if you have a COUGH or FEVER.								
Name	2. Comply with all requirements to enter the site, including temperature checks and hand was	hing.							
Week Start Date	3. Wash your hands regularly throughout the day, using soap and running water for at least 20 seconds. Dry hands afterwards.								
	4. Maintain at least 2m distance from others at all times. If this is not possible because of the tayou are working on or the way the site is set up, speak to your Team Lead or Foreman.	ask							
You are responsible for your own safety, that of	5. Wear the PPE provided to you as instructed. Follow guidance on how to put on, remove, and your PPE. Do not share your PPE with others	d clean							
your colleagues, and of your family and community.	6. Do not share tools unless they have been properly sanitised.								
	7. Do not share drinking vessels, plates, or utensils.								
	8. If you see something which is not safe, inform your Team Lead, Foreman, or HSW Officer.								
Look after your family and	1. Talk to your family about COVID-19. Make sure they know the risks and the symptoms.								
community.	2. Wash as soon as you arrive home.								
	3. Maintain physical distancing outside of the site. Don't go to crowded places.								
	4. If there is a case of COVID-19 in your community, inform your Team Lead or Foreman.								

Umuyobozi w'itsinda/
ushinzwe imirimo yo
kubakisha/uhagarariye
ibikorwa byo
kubakisha

Amazina	
lgihe yatangiriye akazi	

Ufite inshingano zo kubungabunga ubuzima n' imibereho myiza y' abagize itsinda uyoboye mu gihe bari mu kazi.

Inshingano z' ibanze za buri munsi	Umunsi	1	2	3	4	5	6	7
Mbere yo gutangira akazi, genzura ko abakozi bose bambaye ibikoresho by' ubwirinzi nku bisabwa.	ıko							
1. Abakozi bose bagomba kwambara agapfukamunwa, amadarubindi yabugenewe n' uturin	dantoki.							
2. Genzura ko ibikoresho by' ubwirinzi byujuje ubuziranenge.								
<ol> <li>Genzura niba ibikoresho by' ubwirinzi byakorewe isuku nkuko bikwiye/ hakoreshejwe imit yabugenewe.</li> </ol>	i isukura							
<ol> <li>Genzura niba itsinda uyoboye risobanukiwe imikoreshereje y' ibikoresho by' ubwirinzi. Sa amahugurwa y' inyongera mu gihe bibaye ngombwa.</li> </ol>	ıba							
Genzura ko hateganyijwe aho gukarabira intoki hahagije								
<ol> <li>Kora ku buryo haboneka isabuni kandi ihagije, amazi meza n'ibitambaro byo kumutsa into bikoreshwa rimwe.</li> </ol>	oki							
2. Hora ushishikariza abakozi gukaraba intoki kenshi, by' umwihariko mbere yo kurya cg kun	iywa.							
Kora ku buryo abakozi basiga intera ya metero 2 hagati yabo igihe cyose.								
<ol> <li>Tunganya aho gukorera imirimo kuburyo byorohera abakozi gusira intera hagati yabo. Ur kugaragaza aho buri mukozi atagomba kurenga, cyangwa inzira y'icyerekezo kimwe yo ku gusubizayo ibikoresho.</li> </ol>								
2. Koresha imbago cgʻushushanye imbibi hasi aho bishoboka.								
3. Hora wibutsa abakozi akamaro ko gusiga intera hagati yabo n' abandi.								
4. Mu gihe bidashoboka ko abakozi basiga intera hagati yabo ihagije, bitewe n' imiterere y' u uri gukorwa, bimenyeshe ushinzwe imirimo yo kubakisha cg uhagarariye ibikorwa byo ku								
Kora ku buryo buri wese mu itsinda abona ibikoresho bihagije kuburyo ntawukenera gutir mugenzi we, cyangwa ko ibikoresho bisukurwa hakoreshejwe imiti yabugenewe mbere y bihererekanywa.								
Kurikiranira hafi imyitwarire y' abagize itsinda mu gihe cy' akaruhuko kagenwe.								
1. Genzura ko buri wese asiga intera ya metero 2 hagati ye na mugenzi we.		$\Box$	$\Box$	$\Box$	$\Box$	$\Box$	$\Box$	П
<ol><li>Genzura ko abagize itsinda badasaranganya hagati yabo ibikoreshwo byo kunyweramo, amasahani n'ibindi bikoresho byo ku meza.</li></ol>								
Mu gihe hari umukozi urenga nkana ku mabwiriza y' ubwirinzi yashyizweho, bimenyeshe umuyobozi ushinzwe ubuzima n' umutekano w' abakozi cg uhagarariye ibikorwa by' ubwu	ubatsi.							
Mu gihe hari uwo uketseho ko afite ibimenyetso biburira bya koronavirusi (COVID-19) mu bagize itsinda uyoboye, ako kanya kora ku buryo abandi bakozi bamwitarura maze umeny umuyobozi ushinzwe ubuzima n' umutekano w' abakozi cg uhagarariye ibikorwa by' ubwu Hamagara umurongo utishyurwa 114 cyangwa ubimenyeshe umujyanama w'ubuzima cya ivuriro rikwegereye.	yeshe ubatsi.							

# Team Lead / Foreman / Site Engineer

Name		
Week Start Date		

You are responsible for the safety and wellbeing of your team and other teams on the site.

key daily responsibilities	Day	•	2	3	4	5	0	,
Ensure that all workers have PPE as required. (Section 4.3)								
. All workers require MASK, EYE PROTECTION, and GLOVES.								
2. Ensure that PPE is in good condition.								
3. Ensure that PPE has been cleaned / sanitised if necessary.								
I. Make sure your team knows how to use the PPE safely. Ask for more training if necessary.								
Insure that hand washing facilities are available. (Section 4.2 & 4.4)								
. Make sure there is sufficient supply of soap, running water, and single use towels.								
2. Ensure that workers are encouraged to wash their hands regularly, particularly before eating drinking.	or							
Insure that workers maintain 2m distance from each other at all times. (Section 3.0)								
. Organise the work space so that it is easy to maintain distance. For example defined zones for each worker, or one-way systems for delivery of materials.	or							
2. Use physical barriers or markers on the ground where possible.								
3. Regularly remind workers the importance of keeping their distance.								
I. If it is not possible for workers to maintain distance because of the way the task is being performed, speak to the Foreman or Site Manager.								
Ensure that the team has enough tools that they don't need to share, or that tools can be sanit between users. (Section 5.2)	tised							
Continue to monitor team behaviour during welfare breaks.								
. Ensure 2m distance is maintained.								
2. Ensure drinking vessels, plates and utensils are not shared.								
f an individual repeatedly violates protocol, report the violation to the HSW Officer or Site Manager.								
f you suspect an individual on your team has COVID-19 symptoms, immediately isolate them	and							

# Health, Safety & Welfare Officer

Page 1 of 2

Name		
Week Start Date		
Week Start Date		

You are responsible for the health, safety, and welfare of everyone on the site as well as the general public who may be impacted by the works.

Key responsibilities before site re-opens

Set up for health checks at the beginning of each day.	
1. Screened area to maintain workforce privacy	
2. Sufficient infrared thermometers	
3. Register / log for record keeping	
4. PPE for person(s) doing the checks (mask, eye protection, disposable gloves)	
5. Area for queuing marked out with 2m spacing	
Ensure sufficient PPE is available for all workers in addition to that usually required by the task: mask, eye protection, gloves	
Develop protocols for storing and cleaning PPE to minimise cross-contamination.	
Set up sufficient hand washing stations at convenient locations around the site. Make sure a regular supply of running water, soap and single use towels is available.	
Ensure sufficient cleaning materials and disinfectants are available.	
Risk assessments  1. Work with Site Manager / Site Engineers / Foremen to risk assess each task, thinking specifically about infection control requirements.	
2. Ensure that other typical construction risks are not increased as a result of changed working methods or reduced workforce numbers.	
3. Ensure that risk assessments and any changes to working methods are documented and shared with the relevant teams.	
Site organisation  1. Work with Site Manager / Site Engineers / Foremen to set up walking routes and workflows to minimise close contact between personnel: physical barriers, markings on the ground, one way systems, designated areas for outdoor meetings	
Welfare	_
1. Ensure that communal areas (canteens, rest areas etc) are set up such that people can maintain 2m distance.	Н
2. Provide 2m markers for areas where people may queue (e.g. to get food).	Н
3. Ensure handwashing is available at all communal areas.	Н
4. Ensure that sufficient toilets are available for the workforce.	Ц
5. Ensure that cleaning staff are available to clean all communal and welfare areas regularly (at least once per shift, preferably more often).	_ <u>L</u>
Prepare for training sessions  1. Site induction for all personnel, focussing on the risks from COVID-19 and the necessary changes to working practices	
2. Task-specific briefings	
3. Training on how to keep family and community safe	
4. All training sessions to be held in the open air in groups of no more than 10 people	
Prenare site signage / nosters	$\overline{}$

# Health, Safety & Welfare Officer

Page 2 of 2	Ensure that all workers have a health check before entering the site: temperature check, self-declaration of good health, 2m distance to be maintained in the queue			
Name	Monitor workforce entering the site and moving to work zones. Ensure that people are able to enter smoothly and go straight to their place of work without mixing with other teams.			
w .lop.:	Ensure that daily task briefings are carried out.			
Week Start Date	Ensure that all Team Leads and Foremen have the resources they need for their teams to work safely: PPE, handwashing, sufficient space, appropriate working methods and site layout, cleaning or disinfection materials as required, training and understanding.			
	Continuous review of working methods  1. Identify any key areas of risk which had not previously been thought of.  2. Amend working methods as necessary to minimise risks.			
	Deal appropriately with reported H&S violations, including violations of COVID-19 protocols.			
	Ensure that Team Leads and Foremen supervise tasks appropriately, maintaining team discipline and providing appropriate resources.			
	Monitor rest periods or other team movements. Ensure that 2m distance is maintained.			
	Ensure that communal and welfare areas are cleaned at regular intervals.			
	Training  1. Refresher training for workforce on COVID-19 awareness.  2. How to keep your family and community safe.			
	<ol> <li>How to keep your family and community safe.</li> <li>Specific training as required when violations are observed.</li> </ol>			

Deal appropriately with symptomatic personnel, or those who believe they may have been exposed.

Provide space for workforce to report any concerns they have. Ensure concerns are acted upon

Key daily responsibilities

appropriately.

Escalate issues to Site Manager as required.

Site	Manager
Page 1	of 2

Name		
Week Start Date		

You are responsible for the health, safety, and welfare of everyone on the site, as well as the general public who may be affected by the works.

Key responsibilities before site re-opens	ay	1	2	3	4	5	6	7
Ensure appropriate permissions are in place for work to resume, and for personnel to travel to site.	[							
Advise local government leaders of the plan to resume works. Determine appropriate communication methods if a COVID-19 case is confirmed either on site or in the local communit	у.							
Ensure all elements of site set up are in place (see HSW Officer checklist).								
Ensure all teams and personnel have the resources they require.								
Pay particular attention to establishing of physical distancing protocols and PPE provision.								
Work schedule may need to be amended to account for:  Reduced workforce  Time required for putting on and removing PPE  Time required for hygiene protocols  Staggered shifts or break times  Additional training	[							
Ensure all tasks are risk assessed and working methods are amended as necessary (see HSW Officer checklist)								
<ul> <li>Determine protocols for site visitors and deliveries</li> <li>Visitors to be kept to a minimum, allowing essential visits only.</li> <li>Drivers should remain in their vehicles, if the load will allow it. If required to unload goods or materials themselves, they must wash or clean their hands before unloading.</li> <li>Consider developing an electronic signature system with suppliers to reduce physical interaction, for example email or WhatsApp.</li> </ul>								
Provide necessary information to the Site Supervisor:  Planning documentation, including projected numbers of personnel, hygiene provision, cleaning schedules, and planning use of communal areas  Risk assessments  Safe work procedures, allowing for physical distancing and PPE requirements  Schedule of works								
Remember that you too may become sick and be unable to attend site. Make sure there are other who understand how the site runs and can take over in your absence.	rs							

Site	Mar	nager	-
n 0		_	

	Page	2	of	2
--	------	---	----	---

Name		
Week Start Date		

You are responsible for the health, safety, and welfare of everyone on the site, as well as the general public who may be affected by the works.

Key daily responsibilities	Day	1	2	3	4	5	6	7
Communicate with local government leaders to understand the situation in the local area and advise on any changes on site.								Г
Ensure that sufficient resources are available to all teams, Team Leads, Foremen, and HSW Officers to carry out their roles safely.								
Respond appropriately to any emerging situations, for example symptomatic personnel or violations of protocol.								
Ensure that the Site Supervisor is able to carry out their role safely  1. Provide notice of required inspections.								
2. Ensure that area to be inspected is cleared of personnel and sanitised if appropriate.								
3. Ensure that Site Supervisor has appropriate PPE.								
Ensure that site workflows are working as intended, without areas of congestion.								
Ensure that deliveries are carried out safely.								
Recording and reporting  Mandatory daily email for quick review of the day's activities and progress in accordance with the planned schedule, both to:	h							
a. Monitor H&S and QA/QC.								
a. Report any person with COVID-19 symptoms and any cue that can indicate potential present of COVID-19 infection or potential spread.	nce							
Weekly report to include;								
<ul> <li>a. General H&amp;S data (number of workers employed, incidents occured, general site condition key HS &amp; QA actions taken over the course of the week).</li> </ul>	ıs,							
b. Update on the COVID-19 measures in place during the week.								
c. Difficulties that may have been met with regards to infection control (what worked versus what did not) for review and adjustment.								
d. Key aspects to look out for in the uncoming week								

## Site Supervisor

Name	
Week Start Date	


You are responsible for the health, safety, and welfare of everyone on the site, as well as the general public who may be affected by the works.

Key responsibilities before site re-opens	Day	1	2	3	4	5	6	7
Review documentation provided by the Contractor, and ensure that all requirements are met.  As necessary, advise the Contractor on changes, or potentially advise the Client that site should remain closed.	d							
Ensure that safe and legal transport to site is available.								
Ensure sufficient PPE is available for your needs.								
Key responsibilities before site re-opens								
While on site, carry out ad hoc observations of working practices, hygiene and welfare provisio Communicate any unsafe practices to HSW Officer or Site Manager.	n.							
Review Contractor's reporting, and advise on changes required to working methods or site setup.								
Ensure that reported violations or safety concerns are acted upon by the Contractor.								


## Appendix A

# Task Specific Social Distancing Diagrams


#### A.1 Masonry




#### A.2 Carpenty



#### **A.3 Concrete Placements**



#### A.4 Reinforcing Fixing Works



#### A.5 Formwork and Scaffolding Construction

Pending, See A.2 Carpentry Works for similar workflows

#### A.6 Finishing Works (e.g. Plastering, Tile, etc.)

